STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS		
			ROADWAY	BRIDGE	EROSION CONTROL	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND
						0.5	0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-
						0.5	0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
						0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
						0.5	0.5	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
			0.5				0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1				1	LS	TRAFFIC CONTROL (STP 2703(1))	641.10	-
			0.5				0.5	LS	PUBLIC RELATIONS OFFICER	641.12	-
			2				2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			16900				16900	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	112
			15300				15300	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	70
			240				240	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	5
			115				115	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
			1040				1040	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	8
			33800				33800	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	224
			30700				30700	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	240
			480				480	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	10
			230				230	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
			2070				2070	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	6
			940				940	EA	LINE STRIPING TARGETS	646.76	5
					40		40	LB	SEED	651.15	EST.
					250		250	LB	FERTILIZER	651.18	EST.
					1		1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
					1		1	TON	HAY MULCH	651.25	EST.
					25		25	CY	TOPSOIL	651.35	EST.
					200		200	SY	TEMPORARY EROSION MATTING	653.20	EST.
			245				245	SF	TRAFFIC SIGNS, TYPE A	675.20	5.47
			485				485	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	5
			47				47	EA	REMOVING SIGNS	675.50	-
			16				16	EA	ERECTING SALVAGED SIGNS	675.60	-
			4				4	EA	DELINEATOR WITH STEEL POST	676.10	-
			4				4	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
			1				1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
			730				730	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	3

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: DERBY
PROJECT NUMBER: STP 2703(1)

FILE NAME: 07D202.dgn
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: 07C194_30.i

PLOT DATE: 29-JAN-2013 09:2
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 30 OF 62