STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 06

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ALT. U.S. ROUTE 5 (CONTINUED)																																			
												OPTION ITEMS																									
23+79, LT	PHELPS ST. STOP	1	30	30	6.25		1				1					X		X																SIGN ID CODE RI-1	-	SEE FHWA SHS
24+03, RT	CASWELL AVE. MAPLE ST. STOP	1	30	30	6.25		1 1				1					X		X																INSTALL SALVAGED STREET SIGNS 90 DEGREES TO EACH OTHER AND 6 INCHES ABOVE STOP SIGN. SIGN ID CODE RI-1	- - -	- - SEE FHWA SHS
	DERBY LINE	1	72"	12"	6.00																												SIGN ID CODE DI-1		E-123
	NEWPORT	1	72"	12"	6.00																														
24+49, RT	STOP	1	30	30	6.25						1					X		X																SIGN ID CODE RI-1		SEE FHWA SHS
	INTERSTATE 91 5	1 1	24 24	24 24	4.00 4.00																												SIGN ID CODE MI-1 SIGN ID CODE MI-4		E-135 E-136A
25+04, RT	STOP	1	30	30	6.25						1					X		X																SIGN ID CODE RI-1		SEE FHWA SHS
25+50, LT	SOUTH TO	1 1 1 1	24 24 21 21	12 12 15 15	2.00 2.00 2.19 2.19						2					X		X																SIGN ID CODE M3-3 SIGN ID CODE M4-5 SIGN ID CODE M6-1 SIGN ID CODE M6-3		E-135 E-136A E-135 E-136A
ALT. U.S. ROUTE 5 APPROACH DERBY																																			
2+54, RT	STOP	1	30	30	6.25						1					X		X																SIGN ID CODE RI-1		SEE FHWA SHS
3+09, RT	STOP	1	30	30	6.25						1					X		X																SIGN ID CODE RI-1		SEE FHWA SHS
	TSS SHEET 1 SUBTOTALS				37.65		3									75																				
	TSS SHEET 2 SUBTOTALS				44.38											90																				
	TSS SHEET 3 SUBTOTALS				68.25		1									75																				
	TSS SHEET 4 SUBTOTALS				33.00		1									75																				
	TSS SHEET 5 SUBTOTALS				18.75		8									75																				
	TSS SHEET 6 SUBTOTALS				~~37.50~~	65.88	3									~~90~~	120																			
	PROJECT SUBTOTALS				~~239.53~~	305.41	16									~~480~~	510																			
	ROUNDING				5.47		-									5																				
												FT	FT	FT	FT	FT 485	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 245	SF	EA. 16	SF				FT			FT 485					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: DERBY
PROJECT NUMBER: STP 2703(1)

FILE NAME: 07D202.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: 07C194_53.i

PLOT DATE: 29-JAN-2013 09:
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 53 OF 62