

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES				TOTALS		DESCRIPTIONS		
	ROADWAY	EROSION CONTROL	FULL C. E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND
	1			1	CY	COMMON EXCAVATION	203.15	0.1
	1			1	CY	SOLID ROCK EXCAVATION	203.16	0.4
	1			1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
	550			550	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	33
	1			1	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	0.1
	230			230	TON	AGGREGATE SHOULDERS	402.12	6
	90			90	CWT	EMULSIFIED ASPHALT	404.65	2
	1			1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.
	5200			5200	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	54
	1			1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	EST.
	13			13	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
	12			12	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.
	75			75	HR	POWER GRADER RENTAL	608.15	EST.
	75			75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
	25			25	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
	40			40	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
	40			40	HR	TRUCK RENTAL	608.37	EST.
	40			40	HR	LOADER RENTAL, TYPE I	608.40	EST.
		360		360	CY	STONE FILL, TYPE I	613.10	6
		50		50	CY	STONE FILL, TYPE II	613.11	EST.
	15			15	LF	REMOVING AND RESETTING CURB	616.40	3
	9			9	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.9
	6			6	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	0.6
	24			24	SF	DETECTABLE WARNING SURFACE	618.30	-
	14			14	EA	YIELDING MARKER POSTS	619.17	-
	9			9	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
	900			900	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	2700			2700	HR	FLAGGERS	630.15	EST.
			1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
			1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3000	3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
	1			1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
	1			1	LS	TRAFFIC CONTROL	641.10	-
	1			1	LS	PUBLIC RELATIONS OFFICER	641.12	-
	2			2	EA	PORTABLE CHANGABLE MESSAGE SIGN	641.15	-

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
440	SY	MAINLINE BEGIN/END APPROACHES
77	SY	SIDE ROAD APPROACHES
33	SY	ROUNDING
550	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
1855	TON	MAINLINE WEARING COURSE (TYPE IVS)
3091	TON	MAINLINE INTERMEDIATE COURSE (TYPE IIS)
75	TON	SIDE ROADS WEARING COURSE (TYPE IVS)
125	TON	SIDE ROADS INTERMEDIATE COURSE (TYPE IIS)
54	TON	ROUNDING
5200	TON	TOTAL
		STONE FILL, TYPE I
207	CY	DITCH CLEANING
147	CY	SLOPE REPAIR
6	CY	ROUNDING
360	CY	TOTAL

PROJECT NAME: NEWPORT CITY
PROJECT NUMBER: STP 2720(1)

FILE NAME: p07d204.dgn PLOT DATE: 28-NOV-2012 14:51
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: STANTEC
IPARM FILE: p07d204qs01.i SHEET 3 OF 30