ITEM DETAIL SUMMARY SHEET

THIS SHEET NOT USED FOR RECORD PLANS. SEE LAYOUT SHEETS.

LOCATION			MISCELLANEOUS																		REMARKS
BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAVATION CY	203.16 SOLID ROCK EXCAV. CY	301.26 SUBBASE CRUSHED GRAVEL CY	604.40 CHAN ELEV OF DI, CB OR MH EA	604.42 CHANGING ELEV OF SMH EA	613.10 STONE FILL, TYPE I CY	613.11 STONE FILL, TYPE II CY	616.40 REMOVING & RESETTING CURB LF	616.47 BIT. CONC. GUTTERS & TRAFF. ISL. TON	618.10 PORT. CEM. CONC. SIDEWALK, 5 INCH SY	618.30 DET. WARNING SURFACE SF	619.17 YIELDING MARKER POSTS EA	649.31 GEO. UNDER STONE FILL SY							
VT ROUTE 105 NEWPORT CITY																					
0+00	73+12.80	LT&RT				13	12		50					14							QUANTITIES FOR USE AS DIRECTED BY THE RESIDENT ENGINEER
5+46		RT						7							28						ITEMS TO BE USED WITH SLOPE EROSION REPAIR
24+90	27+00	LT						140							498						ITEMS TO BE USED WITH SLOPE EROSION REPAIR
45+14	46+42	RT									8.1										CONSTRUCT BITUMINOUS CONCRETE GUTTER, SEE DETAIL ON MISCELLANEOUS DETAIL SHEET #1
57+68		LT	0.3	0.2	0.3					4		1.8	8								CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
61+58		LT	0.3	0.2	0.3					4		1.8	8								CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
61+93		LT	0.3	0.2	0.3					4		1.8	8								CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
SHEET SUBTOTALS:			0.9	0.6	0.9	13	12	147	50	12	8.1	5.4	24	14	526						
ROUNDING			0.1	0.4	0.1	-	-	-	-	3	0.9	0.6	-	-	-						
SHEET TOTALS			1	1	1	13	12	147 *	50	15	9	6	24	14	526 *						* THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: NEWPORT CITY
PROJECT NUMBER: STP 2720(1)

FILE NAME: p07d204.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07d204idss.i

PLOT DATE: 28-NOV-2012 14:5
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 6 OF 30