STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 06

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
VT ROUTE 105 NEWPORT CITY (CONT)																																			
73+13, RT							~~1~~ 2				1					X 13.25		X															MOUNT SALVAGED SIGN ON NEW POST TWO SIGNS, ARROW AND PLANE	-	-
73+23, LT		1 1	30 24	30 12	6.25 2.00						1					X 14.0'		X															W11-2 (FLUORESCENT YELLOW) W16-7pL (FLUORESCENT YELLOW)		SEE FHWA SHS SEE FHWA SHS
	SHEET SUBTOTALS				8.25											~~30~~ 27.25																			
	TSS SHEET 1				43.51		1									~~105~~ 89.0						-	-												
	TSS SHEET 2				49.11		1									~~135~~ 116.5						-	-												
	TSS SHEET 3				45.59		- 1									~~120~~ 104.25						-	-												
	TSS SHEET 4				53.39		- 1									~~105~~ 90.5						-	-												
	TSS SHEET 5				67.24		-									~~60~~ 50.0						2	~~20~~ 205												
	TSS SHEET 6				8.25		~~1~~ 2									~~30~~ 27.25						-	-												
	PROJECT SUBTOTALS				267.09		~~3~~ 6									~~555~~ 477.5						2	~~20~~												
	ROUNDING				~~2.91~~		-									~~5~~						-	~~4~~												
												FT	FT	FT	FT	FT ~~560~~	FT		EA	LB	LB	LB		LB 205	LB	LB	LB								
	TOTALS				SF ~~270~~ 267.1	SF	EA. ~~3~~ 6	SF				FT			FT ~~560~~ 477.5					LB			EA. 2	LB 205				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: NEWPORT CITY
PROJECT NUMBER: STP 2720(1)

FILE NAME: p07d204.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07d204tss06.i

PLOT DATE: 28-NOV-2012 14:5
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 23 OF 30