QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	GOV'T NON-PARTIC.	FULL CE	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					125	125	CY	COMMON EXCAVATION	203.15	5.7
					85	85	CY	SOLID ROCK EXCAVATION	203.16	6.4
					25	25	CY	EARTH BORROW	203.30	-
					1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
					65000	65000	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	499.7
					100	100	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	5.7
					270	270	CWT	EMULSIFIED ASPHALT	404.65	6.4
					1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
					7150	7150	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	29.2
					1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	11				12	23	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
					79	79	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
					10	10	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
					10	10	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
					56	56	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
					70	70	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
					30	30	HR	POWER BROOM RENTAL TYPE II	608.31	EST
					1800	1800	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	62
					1800	1800	LF	REMOVAL OF EXISTING CURB	616.41	62
					580	580	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	14.3
					1196	1196	SF	DETECTABLE WARNING SURFACE	618.30	-
	21				140	161	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
					1850	1850	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
					3700	3700	HR	FLAGGERS	630.15	EST
		1				1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		3000				3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
					1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
					1	1	LS	TRAFFIC CONTROL	641.10	-
					1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
					3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
					14800	14800	LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406	101
					25700	25700	LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416	277
					2800	2800	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	23
					2175	2175	LF	DURABLE 8 INCH WHITE LINE, RECESSED POLYUREA	646.446	90
					460	460	LF	DURABLE 8 INCH YELLOW LINE, RECESSED POLYUREA	646.456	8

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
64500.3	SY	U.S. ROUTE 7
499.7	SY	ROUNDING
65000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
4873.6	TON	TYPE IVS
		SIDEROADS
627.3	TON	TYPE IVS
		LEVELING COURSE
1619.8	TON	TYPE IVS
29.2	TON	ROUNDING
7150	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2721(1)

FILE NAME: 07d206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
QUANTITY SHEET #1

PLOT DATE: 18-APR-2014 13:51
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 8 OF 70