QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	GOV'T NON-PARTIC.	FULL CE	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					1100	1100	LF	DURABLE 24 INCH STOPBAR, RECESSED POLYUREA	646.486	19
					268	268	EA	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	-
					1775	1775	LF	DURABLE CROSSWALK MARKING, TYPE I TAPE	646.501	8
					29600	29600	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	203
					51200	51200	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	354
					5600	5600	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	46
					4300	4300	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	202
					920	920	LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	16
					2200	2200	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	38
					536	536	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
					3700	3700	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	26
					1150	1150	EA	LINE STRIPING TARGETS	646.76	36
6						6	LB	SEED	651.15	EST
50						50	LB	FERTILIZER	651.18	EST
1						1	TON	AGRICULTURAL LIMESTONE	651.20	EST
54						54	CY	TOPSOIL	651.35	EST
490						490	SY	TEMPORARY EROSION MATTING	653.20	EST
					590	590	SF	TRAFFIC SIGNS, TYPE A	675.20	4.59
					1605	1605	LF	FLANGED CHANNEL SIGN POST	675.301	-
					136	136	EA	REMOVING SIGNS	675.50	-
					47	47	EA	ERECTING SALVAGED SIGNS	675.60	-
					230	230	LF	VEHICLE LOOP DETECTOR	678.22	4
					1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
					1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM (US ROUTE 7 @ MAIN ST.)	900.620	-
					1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM (US ROUTE 7 @ PEARL ST.)	900.620	-
	100					100	LF	SPECIAL PROVISION (DURABLE CENTERLINE MARKING, IMPRINTED/COLORIZED)	900.640	-
	180					180	LF	SPECIAL PROVISION (DURABLE CROSSWALK MARKING, IMPRINTED/COLORIZED)	900.640	4
					1	1	LS	SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) (US ROUTE 7 @ COLLEGE ST.)	900.645	-
					1	1	LS	SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) (US ROUTE 7 @ LOOMIS ST.)	900.645	-
					1	1	LS	SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) (US ROUTE 7 @ MAIN ST.)	900.645	-
					1	1	LS	SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) (US ROUTE 7 @ NORTH ST.)	900.645	-
					1	1	LS	SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) (US ROUTE 7 @ PEARL ST.)	900.645	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2721(1)

FILE NAME: 07d206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
QUANTITY SHEET #2

PLOT DATE: 18-APR-2014 13:51
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 9 OF 70