STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 2

BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAV.	203.16 SOLID ROCK EXCAV.	203.30 EARTH BORROW	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.)	301.26 SUBBASE OF CRUSHED GRAVEL	604.40 CHANGE ELEV. DI	604.412 REHAB. D.I. CLASS I	604.415 REHAB. D.I. CLASS II	604.418 REHAB. D.I. CLASS III	604.42 CHANGE ELEV. SEWER MANHOLE	616.28 CAST-IN-PLACE CONC CURB, TYPE B	616.41 REMOVAL OF EXISTING CURB	618.10 P.C.C. SIDEWALK, 5 INCH	618.30 DETECT. WARNING SURFACE	REMARKS
			CY	CY	CY	CY	CY	EACH	EACH	EACH	EACH	EACH	LF	LF	SY	SF	
46+35	46+39	RT	0.67	0.56			0.67						17	17	4.04	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 1 FROM STANDARD DRAWING C-3A
46+62	46+70	LT	0.64	0.54			0.64						17	17	3.87	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
50+00	50+09	RT	1.22	1.02			1.22						24	24	7.32	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM STANDARD DRAWING C-3A
50+09	50+14	RT	0.46	0.38			0.46						17	17	2.76	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM STANDARD DRAWING C-3A
50+39	50+47	RT	1.17	0.97			1.17						17	17	6.99	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 4 FROM STANDARD DRAWING C-3A
54+22	54+27	RT	0.46	0.38			0.46						17	17	2.76	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
54+54	54+59	RT	0.46	0.39			0.46						17	17	2.79	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
57+47	57+52	RT	0.50	0.42			0.50						17	17	3.00	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 1 FROM STANDARD DRAWING C-3A
57+79	57+85	RT	0.86	0.71			0.86						17	17	5.15	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 1 FROM STANDARD DRAWING C-3A
61+39	61+46	LT	1.05	0.88			1.05						14	14	6.33	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
61+71	61+83	LT	1.20	1.00			1.20						14	14	7.22	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
63+52	63+57	LT	0.49	0.41			0.49						8	8	2.94	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
63+99	64+09	LT	1.32	1.10			1.32						15	15	7.91	18	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
65+24	65+30	LT	0.53	0.44			0.53						6	6	3.20	10	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
65+21	65+33	RT	2.95	2.46			2.95						7	7	17.72	10	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 2 FROM STANDARD DRAWING C-3A
74+52	74+60	LT	1.13	0.94			1.13						12	12	6.77	17	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
74+78	74+89	LT	1.70	1.42			1.70						12	12	10.20	25	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
79+19	79+26	LT	0.72	0.60			0.72						12	12	4.30	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 5, EXAMPLE 2 FROM STANDARD DRAWING C-3A
79+60	79+68	LT	0.73	0.61			0.73						12	12	4.39	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
84+43	84+48	LT	0.44	0.36			0.44						12	12	2.62	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM STANDARD DRAWING C-3A
84+76	84+87	LT	1.78	1.49			1.78						12	12	10.70	10	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3A
																	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM STANDARD DRAWING C-3B
SUBTOTAL			20.48	17.08			20.48						296	296	122.98	226	

ITEM DETAIL SUMMARY SHEET 2

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2721(1)

FILE NAME: 07d206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: 07d206_12.i

PLOT DATE: 18-APR-2014 13:51
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 12 OF 70