STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 5

BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAV. CY	203.16 SOLID ROCK EXCAV. CY	203.30 EARTH BORROW CY	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.) CY	301.26 SUBBASE OF CRUSHED GRAVEL CY	604.40 CHANGE ELEV. DI EACH	604.412 REHAB. D.I. CLASS I EACH	604.415 REHAB. D.I. CLASS II EACH	604.418 REHAB. D.I. CLASS III EACH	604.42 CHANGE ELEV. SEWER MANHOLE EACH	616.28 CAST-IN-PLACE CONC CURB, TYPE B LF	616.41 REMOVAL OF EXISTING CURB LF	618.10 P.C.C. SIDE-WALK, 5 INCH SY	618.30 DETECT. WARNING SURFACE SF	REMARKS
130+51	130+58	RT	0.95	0.79			0.95						17	17	5.71	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM
																	STANDARD DRAWING C-3A
130+78	130+88	RT	1.44	1.20			1.44						17	17	8.64	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM
																	STANDARD DRAWING C-3A
133+27	133+38	RT	1.82	1.51			1.82						29	29	10.90	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
133+65	133+76	RT	1.77	1.48			1.77						28	28	10.63	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+36	137+41	LT	0.57	0.48			0.57						17	17	3.43	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+37	137+42	RT	0.62	0.52			0.62						17	17	3.73	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+46	137+50	LT	0.48	0.40			0.48						17	17	2.88	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+46	137+51	RT	0.45	0.37			0.45						17	17	2.69	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+80	137+85	LT	0.47	0.39			0.47						17	17	2.82	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+80	137+85	RT	0.44	0.36			0.44						17	17	2.62	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+89	137+94	LT	0.63	0.52			0.63						17	17	3.76	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
137+90	137+95	RT	0.80	0.67			0.80						17	17	4.82	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
140+62	140+68	RT	1.01	0.84			1.01						17	17	6.05	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM
																	STANDARD DRAWING C-3A
140+99	141+04	RT	0.40	0.33			0.40						17	17	2.40	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 1, EXAMPLE 2 FROM
																	STANDARD DRAWING C-3A
143+61	143+65	LT	0.55	0.46			0.55						15	15	3.31	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
143+61	143+70	RT	1.49	1.24			1.49						32	32	8.91	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
143+65	143+72	LT	0.61	0.51			0.61						15	15	3.68	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
143+98	144+08	LT	1.57	1.31			1.57						32	32	9.44	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
143+98	144+08	RT	1.49	1.25			1.49						32	32	8.91	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 3 FROM
																	STANDARD DRAWING C-3A
SUBTOTAL			17.56	14.63			17.56						387	387	105.33	192	

ITEM DETAIL SUMMARY SHEET 5

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2721(1)

FILE NAME: 07d206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: 07d206_15.i

PLOT DATE: 18-APR-2014 13:51
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 15 OF 70