STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMMED REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA. 156+33 LT	TRUCK ROUTE						1				1			X																						
	NO PARKING HERE TO CORNER						1																													
STA. 156+55 LT		1	36	36	9.00						2			X																				W3-1A		SHS
STA. 156+63 LT	STOP	1	30	30	6.25						1			X																				R1-1		SHS
STA. 159+50 RT	BIKE ROUTE	1	30	24	5.00						1			X																				D11-1		SHS
	WINOOSKI 1						1																													
	TOTAL THIS SHEET				20.25		3				~~75~~																									
	TSSS 1 TOTAL				~~25.17~~	43.17	~~3~~ 1				~~90~~																									
	TSSS 2 TOTAL				~~42.08~~	60.58	~~2~~ 0				~~105~~																									
	TSSS 3 TOTAL				~~40.83~~	64.83	~~2~~ 4				~~120~~																									
	TSSS 4 TOTAL				~~32.58~~	55.08	3				~~90~~																									
	TSSS 5 TOTAL				25.00		4				~~60~~																									
	TSSS 6 TOTAL				~~27.00~~	45.70	~~5~~ 1				~~75~~																									
	TSSS 7 TOTAL				~~39.25~~	47.03	~~2~~ 0				~~105~~																									
	TSSS 8 TOTAL				~~28.00~~	31.00	1				~~75~~																									
	TSSS 9 TOTAL				~~22.75~~	26.09	~~5~~ 3				~~105~~																									
	TSSS 10 TOTAL				~~28.00~~	31.11	~~2~~ 0				~~75~~	SEE PLACEMENT REPORT																									
	TSSS 11 TOTAL				~~35.75~~	37.42	1				~~90~~																									
	TSSS 12 TOTAL				~~31.25~~	37.81					~~75~~																									
	TSSS 13 TOTAL				~~33.25~~	42.47	3				~~90~~																									
	TSSS 14 TOTAL				~~29.50~~	32.83	3				~~60~~																									
	TSSS 15 TOTAL				~~39.25~~	44.03					~~90~~																									
	TSSS 16 TOTAL				24.00		4				~~45~~																									
	TSSS 17 TOTAL				~~33.50~~	40.06	~~2~~ 0				~~105~~																									
	TSSS 18 TOTAL				~~28.00~~	31.78	~~2~~ 0				~~75~~																									
	TSSS 19 TOTAL				20.25		3				~~75~~																									
	SUBTOTAL				~~585.41~~		~~47~~ 31				~~1605~~	FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	ROUNDING				~~4.59~~		-																													
					SF ~~590~~ 740.24	SF	EA. 47 31	SF			FT ~~1605~~				FT					LB			EA.		LB				EA.	EA.						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 19

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2721(1)

FILE NAME: 07d206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: 07d206_64.i
PLOT DATE: 18-APR-2014 13:53
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 64 OF 70