

# COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT  
AGENCY OF TRANSPORTATION

WINOOSKI STP 2617(I)S				BURLINGTON CITY STP 2727(I)S		BURLINGTON CITY NH 2726(I)S			SUMMARY OF ESTIMATED QUANTITIES					DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES		
BRIDGE	FULL C.E.	TRAINING	ROADWAY	FULL C.E.	ROADWAY	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS
			3						3	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	EST						
			50		40			40	130	CY	COMMON EXCAVATION	203.15	-						
			20		30				50	CY	SOLID ROCK EXCAVATION	203.16	5.25			REFER TO SHEETS 15, 39 AND 58 FOR DETAILED QUANTITY INFORMATION			
			25						25	CY	EARTH BORROW	203.30	EST						
			1						1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-						
			18000		8300			6900	33200	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	466.29						
			40		45			46	131	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	6.04						
			5						5	TON	AGGREGATE SHOULDERS, RAP	402.13	EST						
			75		35			30	140	CWT	EMULSIFIED ASPHALT	404.65	7.62						
			1		1			1	3	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-						
			2000		850			700	3550	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	92.65						
			1		1			1	3	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-						
94			371		70	185		45	765	LF	BRIDGE EXPANSION JOINT, ASPHALT PLUG	516.10	9.75						
			4500		950			7150	12600	LF	JOINT SEALER, HOT POURED	524.11	157.63						
100						100			200	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST						
			2						2	EACH	CHANGE ELEVATION OF DROP INLET, CATCH BASIN, OR MANHOLE	604.40	-						
			13		6			2	21	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-						
			13		6			2	21	EACH	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES CLASS II	604.415	-						
			13		6			2	21	EACH	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES CLASS III	604.418	-						
			25		3				28	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-						
			19		100			100	219	HR	POWER GRADER RENTAL	608.15	EST						
			10		75			75	160	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST						
			14		30			30	74	HR	POWER BROOM RENTAL, TYPE I	608.30	EST						
			7		200			200	407	HR	POWER BROOM RENTAL TYPE II	608.31	EST						
			20		100			100	220	HR	TRUCK RENTAL	608.37	EST						

**COMPOSITE QUANTITY SHEET #1**

PROJECT NAME: BURLINGTON CITY/BURLINGTON CITY WINOOSKI  
 PROJECT NUMBER: NH 2726(I)S & STP 2727(I)S STP 2617(I)S  
 FILE NAME: 07D220.dgn PLOT DATE: 31-OCT-2011 16:43  
 PROJECT LEADER: DOMEY DRAWN BY: PVMT MGMT  
 DESIGNED BY: PVMT MGMT CHECKED BY: PVMT MGMT  
 IPARM FILE: 07D220\_07.i SHEET 7 OF 88