QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				40	40	CY	COMMON EXCAVATION	203.15	0.6
				6900	6900	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	91
				46	46	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	1.8
				30	30	CWT	EMULSIFIED ASPHALT	404.65	3.1
				1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
				700	700	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	24
				1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		185		45	230	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	0.75
				7150	7150	LF	JOINT SEALER, HOT POURED	524.11	37
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
				2	2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
				2	2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.
				2	2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.
				100	100	HR	POWER GRADER RENTAL	608.15	EST.
				75	75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
				30	30	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
				200	200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
				100	100	HR	TRUCK RENTAL	608.37	EST.
				100	100	HR	LOADER RENTAL, TYPE I	608.40	EST.
				100	100	HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST.
				170	170	LF	CAST-IN- PLACE CONCRETE CURB, TYPE B	616.28	2
				131	131	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	0.5
				145	145	SF	DETECTABLE WARNING SURFACE	618.30	5
				6	6	EA	YIELDING MARKER POSTS	619.17	EST.
				1	1	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
				2000	2000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
				2500	2500	HR	FLAGGERS	630.15	EST.
			0.33		0.33	LS	FIELD OFFICE, ENGINEERS	631.10	-
			0.33		0.33	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
			0.33		0.33	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			0.33		0.33	LS	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
				0.33	0.33	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
				1	1	LS	TRAFFIC CONTROL	641.10	-
				0.33	0.33	LS	PUBLIC RELATIONS OFFICER	641.12	-
				2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
				2	2	EA	PORTABLE ARROW BOARD	641.16	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING BITUMINOUS PAVEMENT
6114	SY	MAINLINE
695	SY	SIDE ROADS
91	SY	ROUNDING
6900	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
125	TON	LEVELING COURSE TYPE IVS
492	TON	WEARING COURSE TYPE IVS
59	TON	SIDE ROADS
24	TON	ROUNDING
700	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: BURLINGTON CITY
PROJECT NUMBER: NH 2726(I)S

FILE NAME: 07D220.dgn
PROJECT LEADER: DEG
DESIGNED BY: JPS
IPARM FILE: 07D220_15.i

PLOT DATE: 31-OCT-2011 16:43
DRAWN BY: KAR
CHECKED BY: DWE
SHEET 15 OF 88