QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	40	40	CY	COMMON EXCAVATION	203.15	1.9
	30	30	CY	SOLID ROCK EXCAVATION	203.16	0.4
	8300	8300	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	96
	45	45	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	3.5
	35	35	CWT	EMULSIFIED ASPHALT	404.65	3.5
	1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
	850	850	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	23
	1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	70	70	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	6
	950	950	LF	JOINT SEALER, HOT POURED	524.11	31
	6	6	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
	6	6	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.
	6	6	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.
	3	3	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
	100	100	HR	POWER GRADER RENTAL	608.15	EST.
	75	75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
	30	30	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
	200	200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
	100	100	HR	TRUCK RENTAL	608.37	EST.
	100	100	HR	LOADER RENTAL, TYPE I	608.40	EST.
	50	50	HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST.
	160	160	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	6
	130	130	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	3.9
	235	235	SF	DETECTABLE WARNING SURFACE	618.30	4.7
	18	18	EA	YIELDING MARKER POSTS	619.17	EST.
	5	5	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
	1000	1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	1500	1500	HR	FLAGGERS	630.15	EST.
0.33		0.33	LS	FIELD OFFICE, ENGINEERS	631.10	-
0.33		0.33	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
0.33		0.33	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
0.33		0.33	LS	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
	0.33	0.33	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
	1	1	LS	TRAFFIC CONTROL	641.10	-
	0.33	0.33	LS	PUBLIC RELATIONS OFFICER	641.12	-
	1	1	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
	2	2	EA	PORTABLE ARROW BOARD	641.16	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING BITUMINOUS PAVEMENT
7110	SY	MAINLINE
883	SY	SIDE ROADS
211	SY	DRIVEWAYS
96	SY	ROUNDING
8300	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
153	TON	LEVELING COURSE TYPE IVS
576	TON	WEARING COURSE TYPE IVS
80	TON	SIDE ROADS
41	TON	ROUNDING
850	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: BURLINGTON CITY
PROJECT NUMBER: STP 2727(I)S

FILE NAME: 07D222.dgn
PROJECT LEADER: DEG
DESIGNED BY: JPS
IPARM FILE: 07D222_39.i

PLOT DATE: 31-OCT-2011 16:45
DRAWN BY: KAR
CHECKED BY: DWE
SHEET 39 OF 88