STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75	2.0	2.5	ANCHOR	SLEEVE	SQUARE STEEL lb/ft 1.88	2.42	3.35	TUBULAR ALUMINUM Ø (in) 3.0	4.0	4.0 MOD	TUBULAR ALUMINUM lb/ft 1.3	1.7	1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0	3.5	4.0	5.0	TUBULAR STEEL lb/ft 7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMAINS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																																			
BURLINGTON: 14+45.0, LT	(36" x 36" x 36")	1	-	-	3.90						1			X																													SIGN ID CODE RI-2		E-146
15+54.0, RT	(36" x 36" x 36")	1	-	-	3.90						1			X																													SIGN ID CODE RI-2		E-146
16+18.0, RT	ONLY	1	48	30	10.00						2			X																													SIGN ID CODE VR-934 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS		E-145B
	0070 0403 0031	1	6	10	0.42																																					SIGN ID CODE VD-700		E-138
19+84.0, LT	ONLY	1	48	30	10.00						2			X																													SIGN ID CODE VR-934 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS		E-145B
20+33.0, RT	STOP 0070 0403 0038	1 1	30 6	30 10	6.25 0.42						1			X																													BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
21+39.0, LT	STOP 0070 0403 0041	1 1	30 6	30 10	6.25 0.42						1			X																													BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
23+37.0, RT	HADLEY RD						1																																			SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		
	STOP 0070 0403 0044	1 1	30 6	30 10	6.25 0.42						1			X																													BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
	SHEET SUBTOTAL				48.23		1							70 (56)																																
	ROUNDING				0.77									- (4)																																
												LF	LF	LF 70 (60)	LF	LF	LF		EA.	LB	LB	LB					LB	LB	LB	LB														
	TOTALS				SF 49	SF -	EA. 1	SF -				LF 70 (60)			LF					LB			EA.	LB						EA.	EA.	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET

PROJECT NAME: BURLINGTON CITY
PROJECT NUMBER: STP 2727(I)S

FILE NAME: 07D222.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.P.S.
IPARM FILE: 07D222_52.i
PLOT DATE: 31-OCT-2011 16:45
DRAWN BY: K.A.R.
CHECKED BY: D.W.E.
SHEET 52 OF 88