QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			BRIDGE	FULL E&C	TRAINING	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						3	3	EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-
						50	50	CY	COMMON EXCAVATION	203.15	EST
						20	20	CY	SOLID ROCK EXCAVATION	203.16	5.25
						25	25	CY	EARTH BORROW	203.30	EST
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
						18000	18000	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	279.29
						40	40	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	0.74
						5	5	TON	AGGREGATE SHOULDERS, RAP	402.13	EST
						75	75	CWT	EMULSIFIED ASPHALT	404.65	1.02
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
						2000	2000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	189.3
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
			94			371	465	LF	BRIDGE EXPANSION JOINT, ASPHALT PLUG	516.10	3
						4500	4500	LF	JOINT SEALER, HOT POURED	524.11	89.63
			100				100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
						2	2	EACH	CHANGE ELEVATION OF DROP INLET, CATCH BASIN, OR MANHOLE	604.40	-
						13	13	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						13	13	EACH	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES CLASS II	604.415	-
						13	13	EACH	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES CLASS III	604.418	-
						25	25	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
						19	19	HR	POWER GRADER RENTAL	608.15	EST
						10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						14	14	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
						7	7	HR	POWER BROOM RENTAL TYPE II	608.31	EST
						20	20	HR	TRUCK RENTAL	608.37	EST
						19	19	HR	LOADER RENTAL, TYPE I	608.40	EST
						65	65	LF	VERTICAL GRANITE CURB	616.21	2
						100	100	LF	REMOVING AND RESETTING EXISTING CURB	616.40	EST
						65	65	LF	REMOVAL OF EXISTING CURB	616.41	2
						130	130	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	5.36
						174	174	SF	DETECTABLE WARNING SURFACE	618.30	1.00

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
17391.52	SY	VT ROUTE 15
329.19	SY	US ROUTE 7
279.29	SY	ROUNDING
18000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
1358.03	TON	TYPE IVS
		LEVELING COURSE
452.67	TON	TYPE IVS
189.30	TON	ROUNDING
2000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WINOOSKI
PROJECT NUMBER: STP 2617(1)S

FILE NAME: 06d064.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 06D064_58.i

PLOT DATE: 31-OCT-2011 16:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 58 OF 88