QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL E&C	TRAINING	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		33	33	EACH	YIELDING MARKER POSTS	619.17	-
		30	30	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-
		1400	1400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
		3000	3000	HR	FLAGGERS	630.15	EST
		80	80	HR	FLAGGERS, RAILROAD	630.20	EST
0.34			0.34	LS	FIELD OFFICE, ENGINEERS	631.10	-
0.34			0.34	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
0.34			0.34	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
0.34			0.34	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
	520		520	HR	EMPLOYEE TRAINEESHIP	634.10	EST
		0.34	0.34	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
		1	1	LS	TRAFFIC CONTROL	641.10	-
		0.34	0.34	LS	PUBLIC RELATIONS OFFICER	641.12	-
		5	5	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		5	5	EACH	PORTABLE ARROW BOARD	641.16	-
		10600	10600	LF	DURABLE 4 INCH WHITE LINE, RECESSED TYPE I TAPE	646.407	183
		8700	8700	LF	DURABLE 4 INCH YELLOW LINE, RECESSED TYPE I TAPE	646.417	146
		185	185	LF	DURABLE 6 INCH WHITE LINE, RECESSED TYPE I TAPE	646.427	3
		125	125	LF	DURABLE 6 INCH YELLOW LINE, RECESSED TYPE I TAPE	646.437	1
		1370	1370	LF	DURABLE 8 INCH WHITE LINE, RECESSED TYPE I TAPE	646.447	24
		485	485	LF	DURABLE 8 INCH YELLOW LINE, RECESSED TYPE I TAPE	646.457	10
		320	320	LF	DURABLE 24" STOP BAR, RECESSED TYPE I TAPE	646.487	12
		144	144	EACH	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	-
		490	490	LF	DURABLE CROSSWALK MARKING, RECESSED TYPE I TAPE	646.507	6
		3	3	EACH	DURABLE RAILROAD CROSSING SYMBOL, TYPE I TAPE	646.511	-
		14800	14800	LF	TEMPORARY 4" WHITE LINE, PAINT	646.602	178
		12500	12500	LF	TEMPORARY 4" YELLOW LINE, PAINT	646.612	300
		370	370	LF	TEMPORARY 6" WHITE LINE, PAINT	646.622	6
		250	250	LF	TEMPORARY 6" YELLOW LINE, PAINT	646.632	2
		815	815	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	18

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WINOOSKI
PROJECT NUMBER: STP 2617(1)S

FILE NAME: 06d064.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 06D064_59.i

PLOT DATE: 31-OCT-2011 16:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 59 OF 88