STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
												OPTION ITEMS																								
STA. 36+64 RT	STOP DO NOT ENTER ONE WAY	1	30	30	6.25		2				1					X		X															RI-1		E-143
STA. 37+49 LT		1	24	30	5.00						1					X		X															R4-7		E-144
		1	18	18	2.25																												OMI-1		E-150
STA. 37+94 RT	STOP	1	30	30	6.25						1					X		X															RI-1		E-143
STA. 38+21 LT		1	24	30	5.00						1						X	X															R4-7		E-144
		1	24	24	4.00																												R3-4		E-143
		1	18	18	2.25																												OMI-1		E-150
		1	24	24	4.00																												R3-4		E-143
		1	18	18	2.25																												OMI-1		E-150
STA. 39+04 LT	SPEED LIMIT 25 R	1	24	30	5.00		1				1					X		X															R2-1		E-142
STA. 39+34 LT		1	24	30	5.00						1					X		X															R4-7		E-144
		1	18	18	2.25																												OMI-1		E-150
		1	24	24	4.00																												R3-4		E-143
		1	18	18	2.25																												OMI-1		E-150
STA. 39+46 LT	STOP	1	30	30	6.25						1					X		X															RI-1		E-143
	SUBTOTAL SHEET 82				66.00		7									195																			
	SUBTOTAL SHEET 83				81.17		5									195																			
	SUBTOTAL SHEET 84				64.75		6									150																			
	SUBTOTAL SHEET 85				62.00		3									90	15																		
	SUBTOTAL				273.92							FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	ROUNDING				1.08											630	15																		
					SF 275.00	SF	EA. 21	SF				FT			FT 645					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: WINOOSKI
PROJECT NUMBER: STP 2617(I)S

FILE NAME: 06d064.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 06D064_85.i

PLOT DATE: 31-OCT-2011 16:47
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 85 OF 88