



- SENSOR PLACEMENT NOTES:**
1. A SURFACE SENSOR IS TO BE INSTALLED FOR EACH LOCATION.
 2. A SUBSURFACE SENSOR IS TO BE INSTALLED AT THE MIDDLE SENSOR LOCATION.

- NOTE:**
1. ANY DETAILS FOR INSTALLATION OF THE SENSORS NOT SHOWN ON THIS DRAWING SHALL BE AS PER STANDARD DRAWING E-172.
 2. CONTRACTOR TO BE RESPONSIBLE FOR SAWCUTTING FOR SENSOR PLACEMENT, AS WELL AS PROVIDING PULL STRING IN CONDUIT, CLEANING AND DRYING OF THE SAWCUT AND ASSISTANCE AS NECESSARY FOR PULLING OF SENSOR CABLES. PAVEMENT PREPARATION (I.E. "CHISELING"), RWIS SENSOR PLACEMENT, EPOXY MORTAR PLACEMENT, SENSOR CABLE PULLING AND CABLE CONNECTIONS AT THE CONTROLS TO BE PERFORMED BY THE RWIS EQUIPMENT VENDOR.

MENDON

PROJECT:	FAIR HAVEN: RWIS MENDON: RWIS
FILE NAME:	010001de+2.dgn
PROJECT LEADER:	D. GRAHAVOC
DESIGNED BY:	BMB
RWIS INSTALLATION DETAILS	
PLOT DATE:	10-AUG-2007
DRAWN BY:	MAL
CHECKED BY:	MDL
SHEET	12 OF 12