



**PROJECT LOCATIONS—I-91
(TRAVEL LANE ONLY)**

161.018 - 165.202
 NB MM ~~161.00~~ - 165.20 BARTON-COVENTRY
 NB MM ~~167.20~~ - 168.90 COVENTRY-DERBY
 167.208

NOTES:

1. THE SINGLE PAVEMENT LIFT WEARING COURSE SHALL BE TYPE IV, ITEM 406.25, AS SHOWN ON THE TYPICALS, UNLESS DIRECTED BY THE RESIDENT ENGINEER. ALL LIQUID ASPHALT USED FOR BITUMINOUS CONCRETE PAVEMENT SHALL BE PG 58-34.
2. EMULSIFIED ASPHALT SHALL BE APPLIED ON ALL COLD PLANED SURFACES AT THE RATE OF 0.026 GAL./S.Y. OR AS DIRECTED BY THE RESIDENT ENGINEER.
3. BITUMINOUS CONCRETE PAVEMENT TOLERANCE = 1/4" +/- (TOTAL THICKNESS).
4. COLD PLANING SHALL BE COMPLETED ACCORDING TO TYPICAL OR AS DIRECTED BY THE RESIDENT ENGINEER.
5. DO NOT COLD-PLANE OR PAVE BRIDGES.

**PROJECT
TYPICAL
SHEET**

PROJECT NAME: STATEWIDE
 PROJECT NUMBER: IM RUTF(13)

FILE NAME: /pave/07k008/pk008.dgn PLOT DATE: 15-MAY-2008 08:54
 PROJECT LEADER: WOOLAVER DRAWN BY: JLR
 DESIGNED BY: JLR CHECKED BY: JLR
 pk008ty01.i SHEET 2 OF 7