QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	ROADWAY		QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	45 250		45 250	SY	COLD PLANING-BIT. PAVEMENT	210.10	253
	100		100	CWT	EMULSIFIED ASPHALT	404.65	4
	3 800		3 800	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	51
	1		1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
	175		175	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	350		350	HR	FLAGGERS	630.15	EST.
1			1	LS	TESTING EQUIPMENT--BITUMINOUS	631.17	
	1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
	1		1	LS	TRAFFIC CONTROL	641.10	
	2		2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
	39 000		39 000	LF	6'' WHITE LINE	646.214	60
	400		400	LF	12'' WHITE LINE	646.24	EST.
	39 000		39 000	LF	TEMPORARY 6'' WHITE LINE, PAINT	646.622	60
	400		400	LF	TEMPORARY 12'' WHITE LINE, PAINT	646.662	EST.
	650		650	EA	LINE STRIPING TARGETS	646.76	27
	1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
2669	TON	MM 161.00 ~ 165.20 (I-91 NB)
1080	TON	MM 167.20 ~ 168.90 (I-91 NB)
3749	TON	SUBTOTAL
51	TON	ROUND
3800	TON	TOTAL
		COLD PLANING
32032	SY	MM 161.00 ~ 165.20 (I-91 NB)
12965	SY	MM 167.20 ~ 168.90 (I-91 NB)
44997	SY	SUBTOTAL
253	SY	ROUND
45250	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: STATEWIDE
PROJECT NUMBER: IM RUTF(13)

FILE NAME: /pave/07k008/pk008.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: JLR
/pave/07k008/pk008q01.1

PLOT DATE: 15-MAY-2008 08:
DRAWN BY: JLR
CHECKED BY: JLR
SHEET 3 OF 7