

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
VT ROUTE 105 BRIDGES	BRIDGE NO. 1, VT5A, BURKE	BRIDGE NO. 174, US5, COVENTRY	BRIDGE NO. D08N, TH3, COVENTRY	BRIDGE NO. D08S, TH3, COVENTRY	BRIDGE NO. 12, VT122, WHEELLOCK	BRIDGE NO. 9, VT18, WATERFORD	ROADWAY	FULL CE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
3075	454	467	423	423	454	3236			8532		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
11.58	1.73	2.54	2.2	2.2	2.03	11.44			33.72		CWT	EMULSIFIED ASPHALT	404.65				
835	125	185	160	160	145	815			2425		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
5	1	1	1	1	1	1			11		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
							1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
83	15	20	24	31	11	32			216		GAL	WATER REPELLENT, SILANE	514.10				
380	66	76	68	68	66	124			848		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
1419	216	518	431	431	334	1203			4552		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
1419	216	518	431	431	334	1203			4552		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
50	10	10	10	10	10	10			110		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
50	10	10	10	10	10	10			110		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
5	1	1	1	1	1	1			11		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
12771	1944	4662	3879	3879	3006	10827			40968		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
50	10	10	10	10	10	10			110		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
40	10	48	5	5	10	100			218		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
1500	300	300	300	300	300	700			3700		HR	FLAGGERS	630.15				
								1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							1		1		LS	MOBILIZATION/DEMobilIZATION	635.11				
			1						1		LS	TRAFFIC CONTROL (TH3 - BRIDGE NO. D08N)	641.10				
				1					1		LS	TRAFFIC CONTROL (TH3 - BRIDGE NO. D08S)	641.10				
		1							1		LS	TRAFFIC CONTROL (US5 - BRIDGE NO. 174)	641.10				
	1								1		LS	TRAFFIC CONTROL (VT 5A - BRIDGE NO. 1)	641.10				
5									5		LS	TRAFFIC CONTROL (VT ROUTE 105 BRIDGES)	641.10				
					1				1		LS	TRAFFIC CONTROL (VT122 - BRIDGE NO. 12)	641.10				
						1			1		LS	TRAFFIC CONTROL (VT18 - BRIDGE NO. 9)	641.10				
8	2	2	1	1	2	2			18		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
2129	358	524	463	463	425	1898			6260		LF	4 INCH WHITE LINE	646.20				
2129	358	524	463	463	425	2625			6987		LF	4 INCH YELLOW LINE	646.21				
						225			225		LF	8 INCH YELLOW LINE	646.23				
						25			25		EACH	DURABLE LETTER OR SYMBOL	646.490				
2129	358	524	463	463	425	1898			6260		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
2129	358	524	463	463	425	2625			6987		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
						225			225		LF	TEMPORARY 8 INCH YELLOW LINE	646.650				
						25			25		EACH	TEMPORARY LETTER OR SYMBOL	646.690				
87	15	21	18	18	18	90			267		EACH	LINE STRIPING TARGETS	646.76				
							1		1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				