

QUANTITY SHEET

SUMMARY OF BRIDGE QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
					BLOOMFIELD VT105 BR 96	BLOOMFIELD VT105 BR 97	NEWPORT VT105 BR 57	NEWPORT VT105 BR 58	NEWPORT VT105 BR 59	BRIDGE TOTAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
					534	549	676	676	640	3075	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
					2.19	2.46	2.33	2.59	2.01	11.58	CWT	EMULSIFIED ASPHALT	404.65				
					160	175	170	185	145	835	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
					1	1	1	1	1	5	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
					26	14	19	12	12	83	GAL	WATER REPELLENT, SILANE	514.10				
					86	84	68	70	72	380	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
					317	405	228	330	139	1419	SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
					317	405	228	330	139	1419	SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
					10	10	10	10	10	50	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
					10	10	10	10	10	50	SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
					1	1	1	1	1	5	CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
					2853	3645	2052	2970	1251	12771	SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
					10	10	10	10	10	50	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
					10	10	10	5	5	40	HR	UNIFORMED TRAFFIC OFFICERS	630.10				
					300	300	300	300	300	1500	HR	FLAGGERS	630.15				
					1					1	LS	TRAFFIC CONTROL (VT 105 - BRIDGE NO. 96)	641.10				
						1				1	LS	TRAFFIC CONTROL (VT 105 - BRIDGE NO. 97)	641.10				
							1			1	LS	TRAFFIC CONTROL (VT 105 - BRIDGE NO. 57)	641.10				
								1		1	LS	TRAFFIC CONTROL (VT 105 - BRIDGE NO. 58)	641.10				
									1	1	LS	TRAFFIC CONTROL (VT 105 - BRIDGE NO. 59)	641.10				
					2	2	2	1	1	8	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
					388	409	428	518	386	2129	LF	4 INCH WHITE LINE	646.20				
					388	409	428	518	386	2129	LF	4 INCH YELLOW LINE	646.21				
					388	409	428	518	386	2129	LF	TEMPORARY 4 INCH WHITE LINE	646.600				
					388	409	428	518	386	2129	LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
					15	18	18	21	15	87	EACH	LINE STRIPING TARGETS	646.76				