STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 (2.16)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W SHAPE STEEL FTG. SIZE 24"	W SHAPE STEEL FTG. SIZE 30"	W SHAPE STEEL WEIGHT	W SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																								
STA.010+56.00, RT.		1	6	10	0.42						1					X 9.0																		VD-700		E-13B
STA.018+95.52, LT.		1	48	24	8.00						2					13.33 X 13.92																		WI-6		E-152
STA.021+12.00, RT.		1	6	10	0.42						1					X 8.92																		VD-700		E-13B
STA. 023+86.56, LT.		1	30	30	6.25						1					X 13.50																		RI-1		E-143
STA. 023+86.56, LT.		1	24	30	5.00						1					X 13.50																		VR-017		E-141
STA.027+61.44, RT.		1 1	30 24	30 18	6.25 3.00						1					X 16.0																		WII-2 FLUORESCENT YELLOW GREEN WII-2 PH		E-152
STA.031+68.00, RT.		1	6	10	0.42						1					X 8.92																		VD-700		E-138
STA.033+52.80, RT.		1	30	30	6.25				1							0																		WII-5		
STA.036+85.44, LT.		1 1	30 24	30 18	6.25 3.00						1					X 18.50																		WII-2 FLUORESCENT YELLOW GREEN WII-2PH		E-152
STA.042+50.40, RT.		1	6	10	0.42						1					X 8.75																		VD-700		E-138
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."												FT	FT	FT	FT	FT ~~165~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 45.68	SF	EA.	SF				FT			FT ~~165~~ 124.34				LB			EA.	LB				EA.	EA.	LB						

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 32 OF 75