STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REFLAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA.045+72.48, RT.		1	36	36	9.00						2					14.08 X 14.25																	W3-5		
STA.047+72.48, RT.		1	30	18	3.75						1					X 12.50																	VD-018		E-128B
STA.048+89.28, LT.		1	30	30	6.25				1							0																	W11-5		
STA.049+92.40, RT.		1	36	36	9.00						2					14.0 X 14.25																	W11-8		
STA.052+00.80, RT.		1	24	30	5.00						1					13.50 X																	R2-1		E-142
STA.052+00.80, LT.		1	24	30	5.00						1					X 14.0																	R2-1		E-142
STA.052+90.56, RT.		1	6	10	0.42						1					X 8.83																	VD-700		E-138
STA.~~058+29.12~~ 057+85, RT.		1	24	30	5.00						1					X 13.50																	R4-1		E-141
STA.058+76.64, LT.		1 1	30 36	30 48X48	6.25 5.56						2					X 13.50																	VR-417 W14-3		E-141 E-152
STA.061+45.92, RT.		1	24	30	5.00				1							13.50																	R2-1		E-142
STA.062+30.00, LT.		1	24	30	5.00						1					X 13.33																	R2-1		E-142
STA.063+04.32, RT.		1 1	30 24	30 8	6.25 1.33						1					X 14.58																	S1-1 S4-3		E-153 E-153
STA.063+86.00, LT.		1	36	36	9.00						2					14.08 X 13.58																	W11-8		
												FT	FT	FT	FT	FT ~~225~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 81.81	SF	EA.	SF				FT			FT ~~225~~ 201.48					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 33 OF 75