STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
STA.078+30.00, LT.		1	48	24	8.00						2					12.92 X 12.83																		WI-6		E-152
STA.080+15.04, LT.		1	30	30	6.25						1					X 14.0																		VW-054		E-154
STA.081+36.48, RT.		1	24	30	5.00						1					X 13.33																		VR-017		E-141
STA.081+36.48, RT.		1	30	30	6.25						1					X 13.33																		RI-1		E-143
STA.082+00.00, LT.		1 1 1	30 18 6	30 18 10	6.25 2.25 0.42						1					X 15.58																		WI-2R WI3-1 VD-700	31	 E-155 E-138
STA.082+84.32, RT.		1 1	24 24	12 24	2.00 4.00						1					X 14.42																		M3-1 MI-5		E-136B E-136B
STA.084+58.56, RT.		1 1	24 24	30 30	5.00 5.00				1							16.33																		R2-1 R4-1		E-142 E-141
STA.085+43.04, LT.		1 1	24 24	30 30	5.00 5.00				1							16.33																		R2-1 R4-1		E-142 E-141
												FT	FT	FT	FT	FT ~~105~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT ~~105~~ 129.07					LB			EA.	LB				EA.	EA.	LB					
		TOTALS			SF 60.42	SF	EA.	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 35 OF 75