STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WFIGHT	POST SIZE	SIGNS REQUIRED FRAMED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA.094+11.00, LT.	SPEED LIMIT 35	1	24	30	5.00						1					X 14.0																	R2-1		E-142
STA.094+11.00, RT.	SPEED LIMIT 40	1	24	30	5.00						1					X 13.0																	R2-1		E-142
STA.095+04.00, RT.	0030 1126 0180	1	6	10	0.42						1					X 8.83																	VD-700		E-138
STA.102+43.00, LT.	DO NOT PASS	1	24	30	5.00						1					X 12.50																	R4-1		E-141
STA.102+43.00, RT.	END NO PASSING B-B NO PASSING ZONE	1 1	30 36	30 48X48	6.25 5.56						2					X 13.25																	VR-417 W14-3		E-141 E-152
STA.105+65.28, LT.	0030 1126 0200	1	6	10	0.42						1					X 10.50																	VD-700		E-138
STA.107+75.00, LT.	SPEED LIMIT 40	1	24	30	5.00						1					X 16.25																	R2-1		E-142
STA.107+75.00, RT.	SPEED LIMIT 50	1	24	30	5.00				1							0																	R2-1		E-142
STA.110+37.00, LT.	WELLS N. PAWLET 4	1	30	18	3.75						1					X 14.50																	VD-01B		E-12BB
STA.112+99.20, LT.	SPEED LIMIT 40	1	36	36	9.00						2					15.75 X 15.00																	W3-5		
STA.116+16.00, RT.	0300 1126 0220	1	6	10	0.42						1					X 9.50																	VD-700		E-13B
STA.126+72.00, RT.	0300 1126 0240	1	6	10	0.42						1					X 10.08																	VD-700		E-13B
STA.137+28.00, RT.	0300 1126 0260	1	6	10	0.42						1					X 10.58																	VD-700		E-13B
STA.143+98.56, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00				1																								VR 017		E 141
												FT	FT	FT	FT	FT ~~210~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 56.66	SF	EA.	SF				FT			FT ~~210~~ 163.74					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 36 OF 75