STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	FRAME SIGNS REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA.143+98.56, LT.	STOP	1	30	30	6.25				1							0																	RI-1		E-143
STA.147+84.00, RT.	0300 1126 0280	1	6	10	0.42						1					X 8.83																	VD-700		E-138
STA.158+40.00, RT.	0300 1126 0300	1	6	10	0.42						1					X 7.08																	VD-700		E-138
STA.168+96.00, RT.	0300 1126 0320	1	6	10	0.42						1					X 10.08																	VD-700		E-138
STA.171+35.00, RT.	Y / 25 M.P.H.	1 1	30 18	30 18	6.25 2.25						1					X 13.0																	W1-10L W13-1		E-155 E-155
STA.175+29.60, RT.	B-B	2	18	24	6.00				1							0																	W1-8		E-150
STA. 175+45.44, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00				1							0																	VR-017		E-141
STA. 175+45.44, RT	STOP	1	30	30	6.25				1							0																	R1-1		E-143
STA.176+03.52, RT.		1	18	24	3.00				1							0																	W1-8		E-150
STA.176+35.20, RT.		1	18	24	3.00				1							0																	W1-8		E-150
STA. 176+35.20, RT	STOP	1	30	30	6.25				1							0																	R1-1		E-143
STA.176+56.32, RT.		1	18	24	3.00				1							0																	W1-8		E-150
STA.177+93.60, RT.		1	18	24	3.00				1							0																	W1-8		E-150
STA.179+52.00, RT.	0300 1126 0340	1	6	10	0.42						1					X 8.83																	VD-700		E-138
												FT	FT	FT	FT	FT ~~75~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 51.93	SF	EA.	SF				FT			FT ~~75~~ 47.82					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 37 OF 75