STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 (2.16)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W SHAPE STEEL FTG. SIZE 24"	W SHAPE STEEL FTG. SIZE 30"	W SHAPE STEEL WEIGHT	W SHAPE STEEL POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STA.182+32.00, LT.		1 1	30 18	30 18	6.25 2.25						1					X 17.01																		WI-5L WI3-1		E-155
STA.189+77.92, RT.		1	36	36	9.00						2					15.33 X 15.08																		W3-5		
STA.190+08.00, RT.		1	6	10	0.42						1					X 10.0																		VD-700		E-138
STA.192+56.72, RT.		1 1	30 24	30 18	6.25 3.00	× 2 = 12.50					1					X 13.50																		VW-219 W7-3A	31	 E-152
STA.194+77.92, LT.		1	24	30	5.00				1							0																		R2-1		E-142
STA.194+77.92, RT.		1	24	30	5.00				1							0																		R2-1		E-142
STA.197+20.80, LT.	W/ HORSE SIGN	1	30	30	6.25						1					X 17.0																		VW-054		E-154
STA.200+05.92, LT.		1 1	24 24	12 24	2.00 4.00						1					X 18.0																		M3-3 MI-5		E-136B E-136B
STA.200+64.00, RT.		1	6	10	0.42						1					X 7.50																		VD-700		E-138
												FT	FT	FT	FT	FT ~~120~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT ~~120~~ 113.42					LB			EA.	LB				EA.	EA.	LB					
TOTALS					SF ~~49.84~~ 56.09	SF	EA.	SF																												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 7

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 38 OF 75