STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA.233+27.04, LT.		1	48	24	8.00						2					16.92 X 15.33																		WI-6		E-152
STA.235+48.80, LT.		1 1	30 30	30 30	6.25 6.25						2					17.50 X 18.83																		WI-2L VW-054		E-151 E-154
STA.237+50.00, LT.		1	24	30	5.00						1					X 16.08																		R2-1		E-142
STA.242+08.80, LT.		1	6	10	0.42						1					X 11.0																		VD-700		E-138
STA.248+16.00, LT.		1 1	24 24	24 12	4.00 2.00						1					X 14.83																		R8-3A M4-6		E-143 E-140
STA.248+16.00, RT.		1 1	24 24	24 12	4.00 2.00						1					X 14.50																		R8-3A M4-11		E-143 E-140
STA.251+16.00, RT.		1	30	30	6.25						1					X 14.33																		VW-285		
STA.254+17.92, LT.		1 1	24 6	24 10	4.00 0.42						1					X 12.83																		R8-3A VD-700		E-143 E-138
STA.254+17.92, RT.		1	24	24	4.00						1					X 13.33																		R8-3A		E-143
STA.259+61.76, LT.		1	24	24	4.00						1					X 12.83																		R8-3A		E-143
												FT	FT	FT	FT	FT ~~180~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 56.59	SF	EA.	SF				FT			FT ~~180~~ 178.31					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 9

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 40 OF 75