STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAMEMEN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA.262+83.84, RT.	HIDDEN DRIVES	1	30	30	6.25						1					X 14.08																	VW-060		E-154
STA.264+00.00, RT.	0300 1126 0500	1	6	10	0.42						1					X 9.08																	VD-700		E-138
STA.267+96.00, RT.	R END	1 1	24 24	24 12	4.00 2.00						1					X 13.33																	R8-3A M4-6		E-143 E-140
STA.268+64.64, LT.	POULTNEY WELLS 0300 1126 0509 0300 1117 0000	1 2	72 6	12 10	6.00 0.84						2					13.0 X 13.0																	VD-024 VD-700 VD-700		E-124 E-138 E-138
STA.268+96.32, LT.	R BEGIN	1 1	24 24	24 12	4.00 2.00						1					X 13.83																	R8-3A M4-11		E-143 E-140
STA.268+96.32, RT.	SPEED LIMIT 40	1	24	30	5.00						1					X 13.0																	R2-1		E-142
STA.273+45.00, LT.	SPEED LIMIT 40	1	24	30	5.00						1					X 16.33																	R2-1		E-142
STA.279+21.00, RT.	0300 1117 0020	1	6	10	0.42						1					X 8.67																	VD-700		E-138
STA.288+07.68, LT.	SPEED LIMIT 40	1	24	30	5.00				1							0																	R2-1		E-142
STA.288+07.68, RT.	SPEED LIMIT 50	1	24	30	5.00				1							0																	R2-1		E-142
STA.289+75.64, RT.	0300 1117 0040	1	6	10	0.42						1					X 8.83																	VD-700		E-138
												FT	FT	FT	FT	FT ~~150~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 46.35	SF	EA.	SF				FT			FT ~~150~~ 123.15					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 10

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 41 OF 75