STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WFIGHT	W-SHAPE STEEL POST SIZE	SIGNS REQUIRED FRAMES	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA.332+00.64, RT.	0300 1117 0120	1	6	10	0.42						1					X 9.58																	VD-700		E-138
STA.337+23.36, RT.	NEXT 3 MILES	1 1	30 24	30 18	6.25 3.00						1					X 16.67																	W1-5R W7-3a		E-155 E-152
STA.342+57.00, RT.	0300 1117 0140	1	6	10	0.42						1					X 9.0																	VD-700		E-138
STA.343+09.00, LT.	SUMMER CAMPS AHEAD NEXT 3 MILES	1 1	30 24	30 18	6.25 3.00						1					X 16.08																	VW 344 W7-3a	31	 E-152
STA.353+13.00, RT.	0300 1117 0160	1	6	10	0.42						1					X 10.0																	VD-700		E-138
STA. 354+34.08, LT.	STOP B-B 0300 1117 0165	1 1	30 6	30 10	6.25 0.42						1					X 13.50																	RI-1 VD-700		E-143 E-138
STA. 354+34.08, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00				1							0																	VR-017		E-141
STA. 360+62.40, LT.	STOP B-B 0300 1117 0175	1 1	30 6	30 10	6.25 0.42						1					X 14.0																	RI-1 VD-700		E-143 E-138
STA. 360+62.40, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 13.92																	VR-017		E-141
STA.363+68.96, RT.	0300 1117 0180	1	6	10	0.42						1					X 10.08																	VD-700		E-138
												FT	FT	FT	FT	FT ~~135~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	SF	SF	EA.	SF	FT	FT	LB	EA.	LB	EA.	EA.	LB
	43.52					~~135~~ 112.83						

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 12

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 43 OF 75