STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STA. 398+27.04, LT.	STOP B-B 0300 1117 0247	1 1	30 6	30 10	6.25 0.42						1					X 13.83																	RI-1 VD-700		E-143 E-138
STA. 398+27.04, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 16.67																	VR-017		E-141
STA. 398+27.04, LT.	DEAD END	~~1~~	~~30~~	~~30~~	~~6.25~~		1									0																	W14-1		
STA.405+92.96, RT.	0300 1117 0260	1	6	10	0.42						1					X 9.83																	VD-700		E-138
STA. 410+98.96, RT.		1	30	30	6.25						1					X 16.50																	W1-2R		E-151
STA.416+48.96, RT.	0300 1117 0280	1	6	10	0.42						1					X 9.08																	VD-700		E-138
STA. 421+18.56, RT.		1	30	30	6.25				1							0																	W1-2L	31	
STA. 422+40.00, LT.	NORTH SOUTH VERMONT 30	1 1	24 24	12 24	2.00 4.00						1					X 15.0																	M3-1 M1-5		E-136B E-136B
STA. 425+09.28, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 14.0																	VR-017		E-141
STA. 425+09.28, RT.	STOP B-B 0300 1117 0297	1 1	30 6	30 10	6.25 0.42						1					X 13.0																	RI-1 VD-700		E-143 E-138
												FT	FT	FT	FT	FT ~~120~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF ~~48.93~~ 42.68	SF	EA. 1	SF				FT			FT ~~120~~ 107.91					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 14

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 45 OF 75