STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 425+99.04, RT.	E. POULTNEY 2	1	72	12	6.00						2					10.50 X 12.0																	DI-1A		E-123
STA. 427+31.04, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 11.0																	VR-017		E-141
STA. 427+31.04, RT.	STOP B-B 0300 1117 0301	1 1	30 6	30 10	6.25 0.42						1					X 15.0																	RI-1 VD-700		E-143 E-138
STA.428+10.24, RT.		1	48	24	8.00						2					12.58 X 12.17																	WI-6		E-152
STA. 429+~~68.64~~ 43 RT.	SOUTH NORTH VERMONT 30	1 1	24 24	12 24	2.00 4.00						1					X 11.08																	M3-3 MI-5		E-136B E-136B
STA. 431+05.92, LT.	E. POULTNEY 2	1	72	12	6.00						2					13.08 X 13.17																	DI-1A		E-123
STA. 433+69.92, LT.		1	30	30	6.25				1							0																	WI-2R	31	
STA. 435+17.76, RT.		1	30	30	6.25						1					X 16.0																	WII-6H		E-153
STA.437+60.96, RT.	0300 1117 0320	1	6	10	0.42						1					X 7.0																	VD-700		E-138
STA.439+71.84, RT.	SPEED LIMIT 40	1	36	36	9.00						2					16.0 X 16.0																	W3-5		
												FT	FT	FT	FT	FT ~~195~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 59.59	SF	EA.	SF				FT			FT ~~195~~ 165.58					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 15

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 46 OF 75