STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 441+75.00, RT.	POULTNEY CASTLETON COR. 2	1	30	18	3.75						1					X 13.0																	VD-018		E-128B
STA.443+94.24, RT.	SPEED LIMIT 40	1	24	30	5.00				1							0																	R2-1		E-142
STA.443+94.24, LT.	SPEED LIMIT 50	1	24	30	5.00				1							0																	R2-1		E-142
STA. 447+95.52, LT.		1	30	30	6.25				1							0																	W11-6H		E-153
STA.448+16.96, RT.	0300 1117 0340	1	6	10	0.42						1					X 11.0																	VD-700		E-138
STA. 453+02.40, RT.		1	30	30	6.25						1					X 14.50																	W1-3L		
STA. 456+50.88, RT.		1	48	24	8.00						2					13.50 X 13.67																	W1-6		E-152
STA. 457+40.64, RT.		1	48	24	8.00						2					13.0 X 14.08																	W1-6		E-152
STA.458+72.96, RT.	0300 1117 0360	1	6	10	0.42						1					X 9.0																	VD-700		E-138
STA. 462+58.08, LT		1	48	24	8.00						2					13.0 X 12.58																	W1-6		E-152
STA. 462+73.92, LT.		1	48	24	8.00						2					14.75 X 14.0																	W1-6		E-152
STA. 465+70.00, LT.		1	30	30	6.25						1					X 16.50																	W1-3L		
												FT	FT	FT	FT	FT ~~195~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 65.34	SF	EA.	SF				FT			FT ~~195~~ 172.58					LB		EA.		LB				EA.	EA.					LB	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 16

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 47 OF 75