STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 17

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
OPTION ITEMS																																			
STA. 466+27.68, RT.		1	30	30	6.25						1					X 14.50																		WI-2L		E-151
468+92 STA. ~~469+28.96~~, RT.	0300 1117 0380	1	6	10	0.42						1					X 8.42																		VD-700		E-138
STA. 476+15.04, RT.		1	24	30	5.00						1					X 15.0																		R2-1		E-142
STA. 476+15.04, LT.		1	24	30	5.00				1							0																		R2-1		E-142
STA. 479+84.96, RT.	0300 1117 0400	1	6	10	0.42						1					X 9.0																		VD-700		E-138
STA. 484+33.44, LT.	B-6	2	48	24	16.00						2					13.0 X 13.25																		WI-6		E-152
STA. 484+86.24, RT.		1	36	36	9.00						2					14.17 X 14.42																		W3-5		
STA. 486+12.96, LT.	NEXT 6 MILES	1 1	30 24	30 18	6.25 3.00				1							0																		WI-5R W7-3a		E-155 E-152
STA. 489+61.44, LT.	STATE HIGHWAY BEGINS / SPEED LIMIT 40	1 1	24 24	18 30	3.00 5.00						1					X 16.0																		VR-039 R2-1		E-141 E-142
STA. 489+61.44, RT.	STATE HIGHWAY ENDS / SPEED LIMIT 30	1 1	24 24	18 30	3.00 5.00						1					X 15.33																		VR-038 R2-1		E-141 E-142
												FT	FT	FT	FT	FT ~~150~~	FT		EA	LB	LB	LB		LB	LB	LB	LB							
TOTALS					SF 67.34	SF	EA.	SF				FT			FT ~~150~~ 133.09					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 17

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 48 OF 75