STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA.547+50.00, LT.		1	36	36	9.00						2					17.0 X 19.0																	W3-5		
STA.553+77.00, RT.	0300 1117 0540	1	6	10	0.42						1					X 9.0																	VD-700		E-138
STA.564+33.00, RT.	0300 1117 0560	1	6	10	0.42						1					X 10.0																	VD-700		E-138
STA.574+89.00, RT.	0300 1117 0580	1	6	10	0.42						1					X 10.33																	VD-700		E-138
STA.585+44.64, RT.	0300 1117 0600	1	6	10	0.42						1					X 11.0																	VD-700		E-138
STA.596+01.00, RT.	0300 1117 0620	1	6	10	0.42						1					X 10.08																	VD-700		E-138
STA.606+56.64, RT.	0300 1117 0640	1	6	10	0.42						1					X 10.42																	VD-700		E-138
STA.617+12.64, LT.	0300 1117 0660	1	6	10	0.42						1					X 9.50																	VD-700		E-138
STA.627+69.00, RT.	0300 1117 0680	1	6	10	0.42						1					X 10.33																	VD-700		E-138
STA. 630+96.00, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00				1							0																	VR-017		E-141
STA. 630+96.00, RT.	STOP B-B 0300 1117 0635	1 1	30 6	30 10	6.25 0.42				1							0																	RI-1 VD-700		E-143 E-138
STA. 630+96.00, LT.	STOP B-B 0300 1117 0635	1 1	30 6	30 10	6.25 0.42				1							0																	RI-1 VD-700		E-143 E-138
												FT	FT	FT	FT	FT ~~150~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 30.70	SF	EA.	SF				FT			FT ~~150~~ 116.66					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 19

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 50 OF 75