STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 20

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
STA. 630+96.00, LT.	LEGAL LOAD LIMIT 24,000 POUNDS *	1	24	30	5.00 × 2 = 10				1							12.0 *							* FIRST SIGN INSTALLED WAS STOLEN AND POST DISAPPEARED											VR-017		E-141
STA.638+25.00, RT.	0300 1117 0700	1	6	10	0.42						1					X 9.50																		VD-700		E-138
STA.648+81.00, RT.	0300 1117 0720	1	6	10	0.42						1					X 9.50																		VD-700		E-138
STA.659+37.00, RT.	0300 1117 0740	1	6	10	0.42						1					X 9.50																		VD-700		E-138
STA. 666+81.12, RT.		1	30	30	6.25						1					X 14.0																		W11-6H		E-153
STA.669+93.00, RT.	0300 1117 0760	1	6	10	0.42						1					X 10.0																		VD-700		E-138
STA. 670+34.88, RT.	40 M.P.H.	1 1	30 18	30 18	6.25 2.25						1					X 14.0																		W1-4L W13-1	31	E-155
STA.675+57.60, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 13.0																		VR-017		E-141
STA.675+57.60, RT.	STOP B-B 0300 1117 0770	1 1	30 6	30 10	6.25 0.42						1					X 13.0																		RI-1 VD-700		E-143 E-138
STA. 679+27.20, LT.	STOP B-B 0300 1117 0780	1 1	30 6	30 10	6.25 0.42						1					X 13.08																		RI-1 VD-700		E-143 E-138
STA. 679+27.20, LT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 13.0																		VR-017		E-141
STA.680+49.00, RT.	0300 1117 0780	1	6	10	0.42						1					X 8.50																		VD-700		E-138
												FT	FT	FT	FT	FT ~~165~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF ~~45.19~~ 50.19	SF	EA.	SF				FT			FT ~~165~~ 139.08					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 20

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 51 OF 75