STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA.733+28.64, RT.	0300 1117 0880	1	6	10	0.42						1					X 9.25																	VD-700		E-138
STA. 733+49.26, RT.		1	30	30	6.25						1					X 13.50																	WI-6H		E-153
STA.743+85.00, RT.	0300 1117 0900	1	6	10	0.42						1					X 10.50																	VD-700		E-138
STA. 746+48.64, LT.		1	30	30	6.25						1					X 14.25																	WI-6H		E-153
STA. 746+49.00, RT.		1	30	30	6.25						1					X 15.17																	WI-2L		E-151
STA. 750+59.00, RT.		1	48	24	8.00						2					14.08 X 12.92																	WI-6		E-152
STA. 752+09.00, RT.		1	48	24	8.00						2					12.83 X 12.58																	WI-6		E-152
STA.754+41.00, RT.	0300 1117 0920	1	6	10	0.42						1					X 8.83																	VD-700		E-138
STA. ~~755+99.04~~ 767+00, LT.		1	30	30	6.25						1					X 15.0																	WI-2R		E-151
STA.764+97.00, RT.	0300 1117 0940	1	6	10	0.42						1					X 9.50																	VD-700		E-138
STA. 774+78.72, ~~RT.~~ LT	CASTLETON POULTNEY 0300 1103 0900 / 0300 1117 0930	1 2	72 6	12 10	6.00 0.84						2					14.0 X 14.0																	VD-024 VD-700 VD-700		E-124 E-138 E-138
												FT	FT	FT	FT	FT ~~210~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS			SF 49.52	SF	EA.	SF						FT			FT ~~210~~ 176.41					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 22

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 53 OF 75