STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 777+26.88, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X 13.50																	VR-017		E-141
STA. 777+26.88, RT.	STOP B-B; 0300 1103 0086	1 1	30 6	30 10	6.25 0.42						1					X 13.50																	RI-1 VD-700		E-143 E-138
STA.798+92.68, RT.	STOP B-B; 0300 1103 0086	1 1	30 6	30 10	6.25 0.42						1					X 13.50																	RI-1 VD-700		E-143 E-138
STA.798+92.68, LT.	STOP B-B; 0300 1103 0086	1 1	30 6	30 10	6.25 0.42						1					X 13.0																	RI-1 VD-700		E-143 E-138
STA.817+02.72, RT.	0300 1103 0086	1	6	10	0.42						1					X 9.50																	VD-700		E-138
STA.821+79.52, RT.	SPEED LIMIT 40	1	36	36	9.00						2					15.25 X 15.0																	W3-5		
STA.826+79.52, RT.	SPEED LIMIT 40	1	24	30	5.00						1					X 13.50																	R2-1		E-142
STA.826+79.52, LT.	SPEED LIMIT 50	1	24	30	5.00						1					X 13.50																	R2-1		E-142
STA. 832+12.80, RT.	TRUCKS ENTERING LEFT	1	30	30	6.25						1					X 15.0																	VW-202		E-154
STA. 834+13.44, RT.	HIDDEN DRIVES	1	30	30	6.25						1					X 13.50																	VW-060		E-154
												FT	FT	FT	FT	FT ~~165~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 56.93	SF	EA.	SF				FT			FT ~~165~~ 148.75					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 23

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 54 OF 75