STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED SIGN FRAME	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
STA.842+37.12, RT.	SPEED LIMIT 40	1	24	30	5.00				1							0																	R2-1		E-142
STA. 842+95.00, LT.	HIDDEN DRIVES	1	30	30	6.25						1					X 14.0																	VW-060		E-154
STA. 848+33.76, LT.	TRUCKS ENTERING	1	30	30	6.25						1					X 14.0																	VW-202		E-154
STA. 849+65.76, RT.	JCT VERMONT 4A	1 1	21 24	15 24	2.19 4.00						1					X 14.08																	M2-1 MI-5		E-136B E-136B
STA. 850+60.80, LT.	POULTNEY 6	1	72	12	6.00						2					12.0 X 12.42																	D2-1		E-123
STA. 851+40.00, RT.	↑ BOMOSEEN 3 ↑ MIDDLEBURY 29 ← HYDEVILLE 1 ← FAIR HAVEN 3 CASTLETON 1 → WEST RUTLAND 9 → ← STATE POLICE	6 1	72 72	12 10	36.00 5.00				2							0																	DI-1A DI-1A DI-1A DI-1A DI-1A DI-1A DI-1A DI-1A DI-1SP		E-123 F-123 E-123 E-123 E-123 E-123 E-123 E-123 E-133
STA.852+03.36, LT.	SPEED LIMIT 40	1	24	30	5.00				1							0																	R2-1		E-142
STA. 852+90.00, RT.	WEST EAST VERMONT 4A VERMONT 4A ← → NORTH TO VERMONT 30 4 ↑ ↑	4 4 4	24 24 21	12 24 15	8.00 16.00 8.76						2						17.17 X 17.25	X													XXX	M3-4 MI-5 M6-1 M3-1 MI-5 M6-3 M3-2 MI-5 M6-1 M4-5 MI-4 M6-3		E-136A E-136B
												FT	FT	FT	FT	FT ~~75~~	FT ~~30~~		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 108.45	SF	EA.	SF								FT																			
																FT ~~105~~ 100.92																				
																				LB			FA.			IB			EA.	FA.	IB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 24

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 55 OF 75