STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WFIGHT	W-SHAPE STEEL POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 854+83.20, RT.	NO TURN ON RED / STOP HERE ON RED	1 1	24 24	30 36	5.00 6.00						1					X 16.50																	RIO-IIA RIO-6		E-140 E-140
STA. 854+83.20, LT.	SOUTH VERMONT 30	1 1	24 24	12 24	2.00 4.00						1					X 13.92																	M3-3 MI-5		E-136B E-136B
STA. 855+09.60, LT.	NO TURN ON RED / STOP HERE ON RED	1 1	24 24	30 36	5.00 6.00						1					X 16.58																	RIO-IIA RIO-6		E-140 E-140
STA. 855+83.52, RT.	NORTH VERMONT 30 TO 4	2 2	24 24	12 24	4.00 8.00						2					14.0 X 13.67																XXX	M3-1 M4-5 MI-5 MI-4		E-136B E-136B E-136A E-136A
STA. 856+67.60, LT.	ONLY	1	36	30	7.50						1					X 13.50																	VR-922		E-145A
STA. ~~857+47.52~~ 857+34, RT.	SPEED LIMIT 40	1	24	30	5.00						1					X 13.25																	R2-1		E-142
STA. 857+84.16, LT.	SOUTH VERMONT 30 / WEST VERMONT 4A / EAST VERMONT 4A	3 3 3	24 24 21	12 24 15	6.00 12.00 6.57				2							0																XXX	M3-3 M3-4 M3-2 MI-5 MI-5 MI-5 M6-3 M6-1 M6-1		E-136B E-136B
												FT	FT	FT	FT	FT ~~105~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 77.07	SF	EA.	SF				FT			FT ~~105~~ 101.42					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 25

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 56 OF 75