STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 876+28.00, LT.	CASTLETON CORS. 1 POULTNEY 7	2	72	12	12.00						2					15.25																	D2-1 D2-1		E-123 E-123
	SOUTH VERMONT 30	1	24	12	2.00											X																	M3-3		E-136B
		1	24	24	4.00											17.08																	M1-5		E-136B
STA.876+69.12, CTR	B-B	1	24	30	5.00						1					X																	R4-7 OM1-1		E-144 E-150
		2	18	18	4.50											13.50																	OM1-1		E-150
STA.878+28.00, RT.	SPEED LIMIT 50	1	24	30	5.00						1					X 13.50																	R2-1		E-142
STA.878+28.00, LT.	SPEED LIMIT 40	1	24	30	5.00						1					X 13.58																	R2-1		E-142
STA.880+17.50, CTR	B-B	1	24	30	5.00				1							0																	R4-7 OM1-1		E-144 E-150
		2	18	18	4.50																												OM1-1		E-150
STA. 880+38.72, RT.	NORTH VERMONT 30 ←	2	24	12	4.00						2					15.50																XXX	M3-1	M3-2	E-136B
	SOUTH VERMONT 30 →	2	24	24	8.00											X																	M1-5	M1-5	E-136B
		2	21	15	4.38											15.50																	M6-1	M6-1	E-136B
STA.880+96.80, CTR	B-B	1	24	30	5.00				1							0																	R4-7 OM1-1		E-144 E-150
		2	18	18	4.50																												OM1-1		E-150
STA.880+96.80, LT.	EAST 4 ←	1	24	12	2.00						1					15.25																	M3-2		E-136A
		1	24	24	4.00											X																	M1-4		E-136A
		1	21	15	2.19																												M6-1		E-136A
												FT	FT	FT	FT	FT ~~120~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
				TOTALS	SF 81.07	SF	EA.	SF				FT			FT ~~120~~ 119.16					LB			FA.	LB				EA.	FA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 28

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 59 OF 75