STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 32

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | SIGN DIMENSIONS WIDTH (in) | SIGN DIMENSIONS HEIGHT (in) | NEW & SALVAGED SIGNS "A" | NEW & SALVAGED SIGNS "B" | NEW & SALVAGED SIGNS SALV SIGN | NEW & SALVAGED SIGNS SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | FLANGED CHANNEL lb/ft 2.0 | FLANGED CHANNEL lb/ft 3.0 | SQUARE STEEL (in) lb/ft 2.0 2.16 | SQUARE STEEL (in) lb/ft 2.0 2.42 | SQUARE STEEL (in) lb/ft 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7 | TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7 | FOUND-ATION | TUBULAR STEEL Ø (in) lb/ft 3.0 7.6 | TUBULAR STEEL Ø (in) lb/ft 3.5 9.0 | TUBULAR STEEL Ø (in) lb/ft 4.0 10.8 | TUBULAR STEEL Ø (in) lb/ft 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | W-SHAPE STEEL FTG. SIZE 30" | W-SHAPE STEEL WEIGHT | W-SHAPE STEEL POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | |
| STA.930+00.00, RT. | NEXT 1/2 MILE | 1<br>1 | 30<br>24 | 30<br>18 | 6.25<br>3.00 | | | | | | 1 | | | | | X<br>15.50 | | | | | | | | | | | | | | | | | | WI-3<br>W7-3a | | E-152 |
| STA.939+78.72, RT. | BOMOSEEN HUBBARDTON 4 | 1 | 30 | 18 | 3.75 | | | | + | | 1 | | | | | 13.50 | | | | | | | | | | | | | | | | | | VD-018 | | E-128A |
| STA.947+39.04, LT. | 0300 1103 0328 | 1 | 6 | 10 | 0.42 | | | | | | | | | | | 0 | | | | | | | | | | | | | | | | | | VD-700 | | E-138 |
| STA.953+56.80, LT. | 0300 1103 0340 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | | X<br>9.50 | | | | | | | | | | | | | | | | | | VD-700 | | E-138 |
| STA.959+50.00, LT. | NEXT 1/2 MILE | 1<br>1 | 30<br>24 | 30<br>18 | 6.25<br>3.00 | | | | | | 1 | | | | | X<br>17.08 | | | | | | | | | | | | | | | | | | WI-3<br>W7-3a | | E-152 |
| STA.971+20.32, RT. | BRIDGE 94 VT 30 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | | X<br>10.92 | | | | | | | | | | | | | | | | | | VD-701 | | E-134 |
| STA.973+31.52, RT. | SUMMER CAMP AHEAD NEXT 3 MILES | 1<br>1 | 30<br>24 | 30<br>18 | 6.25<br>3.00 | | | | 1 | | | | | | | 0 | | | | | | | | | | | | | | | | | | VW-219<br>W7-3a | 31 | E-152 |
| STA.978+85.92, LT. | SPEED LIMIT 40 | 1 | 24 | 30 | 5.00 | | | | 1 | | | | | | | 0 | | | | | | | | | | | | | | | | | | R2-1 | | E-142 |
| STA.979+12.32, RT. | SPEED LIMIT 35 | 1 | 24 | 30 | 5.00 | | | | 1 | | | | | | | 0 | | | | | | | | | | | | | | | | | | R2-1 | | E-142 |
| STA.995+54.40, RT. | 0300 1103 0420 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | | X<br>9.0 | | | | | | | | | | | | | | | | | | VD-700 | | E-138 |
| STA.996+38.88, RT. | SPEED LIMIT 35 | 1 | 24 | 30 | 5.00 | | | | 1 | | | | | | | 0 | | | | | | | | | | | | | | | | | | R2-1 | | E-142 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | FT | FT | FT | FT | FT ~~75~~ | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| | **TOTALS** | | | | SF 48.18 | SF | EA. | SF | | | | FT | | | FT ~~75~~ 75.50 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 32

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 63 OF 75