STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 35

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0	2.0	2.5	2.16	2.42	3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	1.3	1.7	1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	3.5	4.0	5.0	7.6	9.0	10.8	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																																
STA. 1063+60.32, RT.	SPEED LIMIT 40	1	24	30	5.00				1							0																										R2-1		E-142
STA. 1063+60.32, LT.	SPEED LIMIT 40	1	24	30	5.00				1							0																										R2-1		E-142
STA. 1066+82.40, LT.	SCHOOL BUS STOP AHEAD	1	30	30	6.25						1					X 17.08																										S3-1		E-153
STA. 1068+19.68, LT.	0300 1103 0556	1	6	10	0.42				1							0																										VD-700		E-138
STA. 1069+20.00, LT.		1	30	30	6.25				1							0																										W2-2M		E-155
STA. 1073+00.16, LT.	SPEED LIMIT 40	1	24	30	5.00						1					X 16.0																										R2-1		E-142
STA. 1073+63.52, RT.	SPEED LIMIT 40	1	24	30	5.00				1							0																										R2-1		E-142
STA. 1080+44.64, RT.	0300 1103 0580	1	6	10	0.42						1					X 10.0																										VD-700		E-138
STA. 1085+25.12, RT.	SPEED LIMIT 40	1	24	30	5.00				1							0																										R2-1		E-142
STA. 1085+56.80, LT.	SPEED LIMIT 40	1	24	30	5.00				1							0																										R2-1		E-142
STA. 1092+16.80, LT.	0300 1103 0600	1	6	10	0.42						1					X 12.0																										VD-700		E-138
												FT	FT	FT	FT	FT ~~60~~	FT		EA	LB	LB	LB		LB	LB	LB	LB														
TOTALS					SF 43.76	SF	EA.	SF				FT			FT ~~60~~ 55.08					LB			EA.	LB				EA.	EA.	LB												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 35

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 66 OF 75