STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 38

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 / 2.16	SQUARE STEEL (in) lb/ft 2.0 / 2.42	SQUARE STEEL (in) lb/ft 2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 / 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD / 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 / 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 / 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 / 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 1174+37.00, LT.		1 1	30 18	30 18	6.25 2.25						1					X 16.08																		WI-2R WI3-1	31	 E-155
STA. 1184+62.00, RT.		1	6	10	0.42						1					X 11.50																		VD-700		E-138
STA. 1195+18.08, RT.		1	6	10	0.42						1					X 9.50																		VD-700		E-138
STA. 1205+74.08, LT.		1	6	10	0.42						1					X 11.0																		VD-700		E-138
STA. 1216+45.92, RT.		1	6	10	0.42						1					X 9.58																		VD-700		E-138
STA. 1222+42 ~~1223+17.00~~, RT.		1	30	30	6.25						1					X 16.50																		W2 2M		E-155
STA. 1227+65.28, LT.		1 1	24 24	12 24	2.00 4.00						1					X 15.0																		M3-3 MI-5		E-136B E-136B
STA. 1229+76.48, RT.		1 1	24 24	12 24	2.00 4.00						1					X 14.50																		M3-1 MI-5		E-136B E-136B
STA. 1236+25.00, LT.		1	30	30	6.25						1					X 15.50																		W2-2M		E-155
STA. 1237+54.00, LT.		1	6	10	0.42						1					X 9.50																		VD-700		E-138
												FT	FT	FT	FT	FT ~~150~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 35.10	SF	EA.	SF				FT			FT ~~150~~ 128.66					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 38

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 69 OF 75