STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 39

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WFIGHT	POST SIZE	SIGNS REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA. 1247+98.00, ~~LT.~~ RT	0300 1108 0240	1	6	10	0.42						1					X 9.0																	VD-700		E-138
STA. 1257+00.96, RT.	HUBBARDTON GULF	1	30	18	3.75						1					X 14.50																	VD-018		E-128A
STA. 1258+54.00, LT.	0300 1108 0260	1	6	10	0.42						1					X 8.08																	VD-700		E-138
STA. 1269+10.08, RT.	0300 1108 0280	1	6	10	0.42						1					X 10.50																	VD-700		E-138
STA. 1276+38.00, LT.	HIDDEN DRIVE RIGHT SCHOOL BUS STOP AHEAD	1 1	30 30	30 30	6.25 6.25						2					11.25 X 12.75																	VW-054 S3-1		E-154 E-153
STA. 1279+66.0, LT.	0300 1108 0300	1	6	10	0.42						1					X 10.25																	VD-700		E-138
STA. 1290+22.00, RT.	0300 1108 0320	1	6	10	0.42						1					X 10.50																	VD-700		E-138
STA. 1296+82.08, LT.	10%	1	30	30	6.25						1					X 14.50																	W7-1		E-152
STA. 1299+30.24, LT.	HUBBARDTON GULF	1	30	18	3.75						1					X 13.0																	VD-018		E-128A
STA. 1300+78.00, RT.	0300 1108 0340	1	6	10	0.42						1					X 10.0																	VD-700		E-138
												FT	FT	FT	FT	FT ~~165~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 28.77	SF	EA.	SF				FT			FT ~~165~~ 124.33					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WELLS-HUBBARDTON
PROJECT NUMBER: STPG SIGN (15)

FILE NAME: stpg sign15 sums.dgn
PROJECT LEADER: N.AVERY
DESIGNED BY: N.AVERY
TRAFFIC SIGN SUMMARY SHEET 39

PLOT DATE: 04-AUG-2008
DRAWN BY: ROADWAY
CHECKED BY: A.GAMBLE
SHEET 70 OF 75