QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
7,500		7,500	LF	SHOULDER BERM REMOVAL	203.40	EST.
20		20	CWT	EMULSIFIED ASPHALT	404.65	EST.
250		250	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	490.30	EST.
175		175	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
200		200	HR	FLAGGERS	630.15	EST.
	0.5	0.5	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	EST.
0.5		0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST.
0.5		0.5	LS	TRAFFIC CONTROL	641.10	EST.
37,000		37,000	LF	4 '' WHITE LINE	646.20	EST.
35,000		35,000	LF	4 '' YELLOW LINE	646.21	EST.
37,000		37,000	LF	TEMPORARY 4 '' WHITE LINE, PAINT	646.602	EST.
35,000		35,000	LF	TEMPORARY 4 '' YELLOW LINE, PAINT	646.612	EST.
475		475	EA	LINE STRIPING TARGETS	646.76	EST.
14000		14,000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS ✳	646.85	EST.
10,000		10,000	LB	SPECIAL PROVISION (BITUMINOUS CRACK SEALING, BLOW AND GO METHOD)	900.635	EST.
59,000		59,000	SY	SPECIAL PROVISION (ASPHALT-RUBBER SURFACE TREATMENT WITH AGGREGATE COVER)	900.675	EST.
15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

✳ REVISED 07-11-08

PROJECT NAME: HARDWICK
PROJECT NUMBER: STP SURF(9)

FILE NAME: p08b014.dgn
PROJECT LEADER: TED DOMEY
DESIGNED BY: WILDER
p08b014qs.1

PLOT DATE: 20-AUG-2009 14:4
DRAWN BY: WILDER
CHECKED BY: PAVT MGMT
SHEET 10 OF 12