



## CONSTRUCTION APPROACH SIGNING

SEE STD. E-100 FOR SIGN PLACEMENT

THE RESIDENT ENGINEER, AT HIS OR HER DISCRETION,  
MAY ELIMINATE CONSTRUCTION APPROACH SIGNING AT  
DEAD END LOCATIONS

### LEGEND

RWA = ROAD WORK AHEAD  
 RW500 = ROAD WORK 500 FEET  
 EW = END WORK  
 RWN = ROAD WORK NEXT 4 MILES

1. PAYMENT FOR CONSTRUCTION SIGNING WILL BE MADE UNDER CONTRACT ITEM 64I.I0.

U.S. HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
BAILEY RD. (T-60)	1	1			
ROUTE 16	1	1			
EASTMAN RD. (T-54)	1	1			
<del>FISHER RD. (T-53)</del> OLD HOUSE DR	1	1			
BEGINNING OF PROJECT	2	2	2	1	
END OF PROJECT	2	2	2	1	
TOTAL	8	8	4	2	

+ BROWN FARM 1 1

### TEMPORARY TRAFFIC CONTROL PLAN

PROJECT NAME: HARDWICK  
 PROJECT NUMBER: STP SURF(9)

FILE NAME: p08b014.dgn  
 PROJECT LEADER: TED DOMEY  
 DESIGNED BY: WILDER  
 p08b014+tp.i

PLOT DATE: 20-AUG-2009 14:  
 DRAWN BY: WILDER  
 CHECKED BY: PAVT MGMT  
 SHEET 12 OF 12