

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1		1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
									1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									10		10		HR	POWER BROOM RENTAL, TYPE II	608.31				
									2		2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
									1900		1900		LF	TEMPORARY TRAFFIC BARRIER	621.90				
									3800		3800		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
									250		250		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
									500		500		HR	FLAGGERS	630.15				
									1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
									1		1		LS	TRAFFIC CONTROL	641.10				
									2		2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
										100	100		LB	SEED	651.15				
										700	700		LB	FERTILIZER	651.18				
										5	5		TON	AGRICULTURAL LIMESTONE	651.20				
										5	5		TON	HAYMULCH	651.25				
									1000		1000		CY	TOPSOIL	651.35				
										1	1		LS	EPSC PLAN	652.10				
										10	10		HR	MONITORING EPSC PLAN	652.20				
										1	1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
										4000	4000		SY	TEMPORARY EROSION MATTING	653.20				
										33	33		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
										2	2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
										1400	1400		LF	PROJECT DEMARCATION FENCE	653.55				
									1200		1200		CY	SPECIAL PROVISION (REMOVAL OF LEDGE SALVAGE MATERIAL)	900.608				
									10		10		CY	SPECIAL PROVISION (SHOTCRETE)	900.608				
									150		150		CY	SPECIAL PROVISION (TRIM BLASTING, TRUCK MEASUREMENT)	900.608				
									80		80		HR	SPECIAL PROVISION (HAND SCALING)	900.630				
									100		100		LF	SPECIAL PROVISION (ROCK ANCHOR)	900.640				
									1560		1560		LF	SPECIAL PROVISION (ROCK DOWELING)	900.640				
									500		500		LF	SPECIAL PROVISION (ROCK DRAIN)	900.640				
									100		100		LF	SPECIAL PROVISION (ROCK NAIL FOR SHOTCRETE)	900.640				
									1		1		LS	SPECIAL PROVISION (ROCK ANCHOR TESTING)	900.645				
									1		1		LS	SPECIAL PROVISION (ROCK DOWEL TESTING)	900.645				

PROJECT NAME: CHESTER
 PROJECT NUMBER: NH 025-1(41)
 FILE NAME: d08b036frm.dgn
 PROJECT LEADER: K. ROBIE
 DESIGNED BY: P. PELOQUIN
 QUANTITY SHEET
 PLOT DATE: 23-NOV-2009
 DRAWN BY: P. PELOQUIN
 CHECKED BY: S. MENARD
 SHEET 5 OF 16