

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C E ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
									55		55		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							10				10		CY	GRANULAR BORROW	203.32				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									65		65		CY	STRUCTURE EXCAVATION	204.25				
									50		50		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									2110		2110		LB	REINFORCING STEEL (FPQ)	507.15				
									1		1		GAL	WATER REPELLENT, SILANE	514.10				
									20		20		CY	CONCRETE, CLASS B (FPQ)	541.25				
									5		5		CY	CONCRETE, CLASS D	541.31				
							7				7		LF	6 INCH UNDERDRAIN PIPE	605.10				
									10		10		CY	STONE FILL, TYPE I	613.10				
									45		45		CY	STONE FILL, TYPE IV	613.13				
							300				300		HR	FLAGGERS	630.15				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1				1		LS	MOBILIZATION/DEMOLITION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
									62		62		SY	GEOTEXTILE UNDER STONE FILL	649.31				
									25		25		SY	GRUBBING MATERIAL	651.40				
								165			165		LF	PROJECT DEMARCATION FENCE	653.55				
									64		64		LF	SPECIAL PROVISION (ALUMNUM PIPE LINER)(60")(EXISTING 72" PIPE)	900.640				
									1		1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)	900.645				
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				

PROJECT NAME: STRATTON  
PROJECT NUMBER: STP CULV(12)  
FILE NAME: s08b058excel.dgn PLOT DATE: 05/21/2010  
PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARD  
DESIGNED BY: H.I.SALLS CHECKED BY: H.I.SALLS  
QUANTITY SHEET #1 SHEET 3 OF 15